



Denniston  
Pit # 58-009  
15203 S. Telegraph  
Monroe, MI 48161  
(734) 241-8966

06/08/2017

### 2116-Seepage Bed

Procedure	Sieve/Test	Average	Unit
	1 1/2" (37.5mm)	100.0	%
	1" (25mm)	100.0	%
	3/4" (19mm)	78.9	%
	1/2" (12.5mm)	36.1	%
	3/8" (9.5mm)	17.0	%
	#4 (4.75mm)	2.2	%
	#8 (2.36mm)	1.4	%
	Pan	0.00	%
	Grad Loss	0.000	%
	Wash Loss (#200/75um)	1.0	%