

All Sampling and testing are preformed with accordance ASTM Section 4 Construction Volume 4.02 and MDOT

Procedure	Sieve/Test	Average	Unit	MDOT 6AA
	1 1/2" (37.5mm)	100.0	%	100-100
	1" (25mm)	99.3	%	95-100
	3/4" (19mm)	79.5	%	
	1/2" (12.5mm)	44.0	%	30-60
	3/8" (9.5mm)	26.4	%	
	#4 (4.75mm)	5.6	%	0-8
	#8 (2.36mm)	2.8	%	
	Wash Loss (#200/75um)	1.3	%	0.0-2.0
ASTM C70	Total Moisture	4.2	%	

All Sampling and testing are preformed with accordance ASTM Section 4 Construction Volume 4.02 and MDOT