



Ottawa Lake
ASI # 58-003
7555 Whiteford Rd
Ottawa Lake, MI 49267

04/30/2021

All sampling and testing are performed in accordance with ASTM Section 4 Construction volume 04.02 and MDOT Standard Specification for Construction 2012.

2049-Intermediate Agg. Limestone

Procedure	Sieve/Test	Average	Unit	Intermediate Agg.
	3/4" (19mm)	100.0	%	100-100
	1/2" (12.5mm)	92.3	%	80-95
	3/8" (9.5mm)	80.9	%	70-85
	#4 (4.75mm)	25.2	%	15-28
	#8 (2.36mm)	5.6	%	0-8
	#16 (1.18mm)	3.2	%	
	#30 (.6mm)	2.4	%	
	#50 (.3mm)	2.1	%	
	#100 (.15mm)	2.0	%	
	#200 (75µm)	1.95	%	
	Wash Loss (#200/75um)	1.8	%	0.0-3.0

All sampling and testing are performed in accordance with ASTM Section 4 Construction volume 04.02 and MDOT Standard Specification for Construction 2012.

Name/Title

Josh Orshoski / QC Tech